

Time Impact Analysis

Effective Techniques for Analyzing Construction Schedule Delays

ace-consulting.net





Delay Review Agenda

1. Analysis of Progress Schedule

2. Preparation of Delay Schedule


3. Proper Cadence of Creating Delay Schedule

4. Understanding CPM Schedule Delay



Construction Delays

We have a construction delay now what?
Understanding the delay and when the delay was realized.





Required Actions Before Starting....

- 1. Need a schedule that has **correct logic and sequencing** corresponding to what is happening in the field prior to delay.
- 2. Need a schedule that has been **updated monthly** with correct actual start and finish dates.
- 3. Documentation & timeline of the delay event in detail.
 - Dates in chronological order of everything that happened
 - The 3 D's.... Documentation, Documentation, & Documentation
 - RFI's, PCO's, RFP's, related to delay if any with dates submitted and approved/answered.
 - Scope of work for delay or change in detail with sequencing to input into the schedule to show delay if add scope etc.
 - How the delay is related to activities in the original schedule in order to tie logic to the delay fragnet.
 - Ie. Roof delay is causing the slab on grade to not be poured because of the roof not being dried in.


Time Impact Analysis

"The TIA is a 'forward looking', prospective schedule analysis technique that adds a modeled delay to an accepted contract schedule to determine the possible impact of that delay to project completion."


- AACE International Recommended Practice No. 52R-06



Delay Event




Delay Analysis – Time of Application






Recommended Practice 56r-06 Prospective Time Impact Analysis
Recommended Practice 29r-03 Forensic Schedule

Time Impact Analysis Process







Prospective Analysis

Contemporaneous Prospective

- 1. Performed to "look-ahead" during project.
- 2. Performed at moment of start of impact.
- 3. Called Contemporaneous Time Impact Analysis (TIA)
- 4. Compare the predicted completion of the schedule just prior to the date of the "delay event" to the predicted completion of the schedule after inserting a fragnet of impact activities into the schedule.



Retrospective Analysis

Forensic(Retrospective Analysis)

- 1. Performed after the project or delay event.
- 2. Typically used in delay analysis in claims.
- 3. No industry standard name.
- 4. Retrospective, backward-looking.
- 5. Sometimes also called Contemporaneous TIA since analysis is done from the beginning of the impact even though it is analyzed after the fact.

Reasons for Use

Occasionally mandated by specification.

Best way to evaluate expected impacts resulting from changed conditions.

Supports negotiation of time extensions due to changed conditions.

Enables sharing of risk.

Keeps project on track with accurate schedule.



Golden Rules



SCHEDULES MUST REMAIN **DYNAMIC**.



IMPACTS ARE EVALUATED CHRONOLOGICALLY.



THE SUM OF ALL IMPACTS ARE **CUMULATIVE**.



PROSPECTIVE (FORWARD LOOKING) ANALYSIS.



THE PROJECT'S CRITICAL
PATH MUST BE IMPACTED,
AND THE PROJECT
COMPLETION DATE MUST
BE DELAYED TO BE
ENTITLED TO A TIME
EXTENSION.



Required Actions Before Starting the TIA



Baseline or Initial Progress schedule that is reasonable and approved/accepted by the owner.



The contractor must perform regular progress updates to the schedule, which accurately reflect work on the project.



Facts pertaining to the changed condition or impact are available.



Steps for Preparing a TIA

1. Verify Schedule (Current Schedule)

- Test for reasonableness.
- Ensure schedule logic models the actual project sequencing.

2. Check for Constraints

- If constraints exist, establish methodology.
- Remove the constraints, if possible.
- Insert logic to replace constraints.
- Verify accuracy of changes.
- Document use of methodology.



3. Update the Current Schedule

- Use update data through the date that will reflect the situation immediately prior to the beginning of the changed condition.
- **Please Note: Do not make any logic changes after the update.

4. Calculate the Schedule

 Set Data Date immediately prior to the beginning of the changed condition (match update data).

5. Document the Completion Date

- Use a common activity such as Substantial Completion (preferable), or an Interim Milestone, as necessary.
- Use Early Finish of the entire project.
- Be consistent in choosing the comparison activity.

6. Identify the Reason for Preparing a TIA

- Changed condition.
- Potential delay situation.
- Other actions beyond Contractor's control.



- 7. Create Copy of the Reference Schedule for Use in the Analysis
 - Done so that the reference schedule can be used as a target.
- 8. Determine Scope of Work Required to Deal with Changed Condition
 - List Assumptions:
 - Scope of Work
 - Manpower and Resources
 - Sequencing Rationale
 - **Note any questionable assumptions.



9. Create Fragnet of Activities

- Estimate durations and document.
- Determine appropriate connection points between predecessors and successor.
- (Which activities are affected by the changed condition?)
 - Insert fragnet with new logic connections.
 - AACE Recommended Practice "Set the duration of the delay activities to zero and recalculate the CPM."

10. Provide Narrative – Detailing how the work will be done

11. Recalculate Project

12. Compare Results to Updated Schedule Completion Dates Prior to Insertion



13. Review Critical Path Changes and Shifts

- Identify CP in schedule prior to TIA insertion
- Identify CP in schedule after TIA insertion
- Compare and review changes

14. Write Up Conclusions

15. Be Prepared to Discuss and Defend



After the TIA

After TIA submittal and review:

- 1. Negotiate time extension, if any.
- 2. Document the decision.
- 3. If justified, incorporate TIA into schedule.
- 4. Publish revised schedule with new completion dates.
- 5. Provide change order showing settlement.
- 6. Ideally, TIA resolution should conclude any known delay issues or impacts to date.



Benefits of TIA's

Benefits to Owner

- Participates in decisions that affect budget and completion.
- Can negotiate requests for time and costs prior to work.
- Encourages cooperation.
- No lingering potential claims issues.
- Budget and completion information always current and reasonably accurate.
- Allows Owner to take advantage of pacing opportunities.
- Reduce or eliminate need for unilateral modifications.
- Shares performance and cost risk.




Benefits of TIA's

Benefits to Contractor

- Relatively simple analyses when compared to claims.
- Receives timely time extensions.
- Builds good documentation, even if rejected.
- Allows negotiation prior to spending money or doing work.
- Minimal memory problems compared to old issues.
- Allows for pacing other trades.
- Costs for TIA effort should be reimbursable.
- Fair preparation of TIA builds credibility.
- Builds in understanding of risk in pricing.





Example Problem ACE301 Prefab Building

Typical construction project.


Work includes erection of prefabricated buildings on concrete foundations, electrical, mechanical and landscaping.

Contractor has an approved Baseline Schedule and submits regular schedule updates with the pay estimates.

Baseline Schedule

lata Date 25-Jan-22		- V			Baseline Examp										Run Date 65-Jun-24			
Ivity ID	Activity Name	Dig Dur	Rem Dur	Steri	Finish	Phy %	Total Float	nel 2022 Feb Mar Apr Mey Jun Jul Aus Sep					Del Nev					
Total		157	157	25-Jan-22	30-Jun-22		0	140	3.807	/Gt May	Just		+22, Tota		- Cu	1999	+	
Baseline Examp	Ne ACE301	157	157	25-Jan-22	30-Jun-22		0	-		_	_	→ 30-Jur	22. Bas	eline Exa	mple ACI	301	i	
Milestones	NO 110 E 00 1	157	157	25-Jan-22	30-Jun-22		0	-	-	_		→ 30-Jur	-22, Mile	stones			1	
MILE-1000	Notice to Proceed	0	0	25-Jan-22*	OF GUITEE	0%	0	Notice t	Proceed			1					i	
MILE-1010	CCD- Contract Completion Date	0	0	LU UUIT LL	30-Jun-22*	0%	0	1000000	10000			CCD-	Contract	Completi	on Date		į	
Pre-Construction		89	89	25-Jan-22	31-May-22	0.10	0		·		31-Ma	v-22. Pre					-	
Submittal Development		5	5	25-Jan-22	31-Jan-22		1	₹ 31-Ja	-22. Subr	nittal Develop	nent	1					3	
SDEV-1000	Submit Div 3- Concrete Submittal	1	1	25-Jan-22	25-Jan-22	0%	72	Submit	Div 3- Cor	crete Submitt	al	1		1				
SDEV-1010	Submit Prefab Bldg Shops	5	5	25-Jan-22	31-Jan-22	0%		Subm	k Prefab B	lda Shobs		1		1				
	iew & Approval	9	g	26-Jan-22	07-Feb-22	370	64	07-6	Feb-22. Su	bmittal Review	& Approv	ai		1				
R&A-1000	R/A Div 3- Concrete Submittal	1	-1	26-Jan-22	26-Jan-22	0%	72	- 1 V (CO)		te Submittal			·	·	·			
R&A-1010	R/A Prefab Bldg Shops	5	5	01-Feb-22	07-Feb-22	0%	0	R/A	Prefab Blo	a Shoos		1		1				
Long Lead Pro		79	79	08-Feb-22	31-May-22	070	0	-		3	31-Ma	v-22 Lor	o Lead F	ocurem	ent			
FAB-1000	Fabricate & Deliver Prefab Bldg	79	79	08-Feb-22	31-May-22	0%	0				Fabric	ate & De	liver Pref	ab Bida				
Construction	1 danielie de Deires i Teles biog	99	99	25-Jan-22	14-Jun-22	910	0	1000			1	Jun-22.		100000000000000000000000000000000000000				
Site Prep		5	5	25-Jan-22	31-Jan-22		0	▼ 31-Ja	n-22, Site	Prep								
MOB-1000	Site Survey	1	- 1	25-Jan-22	25-Jan-22	0%	0	Site Su	40 1	1000		1		1				
MOB-1010	Clear & Grub	3	3	26-Jan-22	28-Jan-22	0%	0	Clear 8		1				1				
MOB-1020	Install Erosion Control	3	3	27-Jan-22	31-Jan-22	0%	0	Install	Erosion C	ontrol		1	10	1				
Foundations & Structure		94	94	01-Feb-22	14-Jun-22	0.0	0	-	8		14	Jun-22.	Foundati	ons & Str	ucture			
NST-1000	Set OH Power Poles	19	19	01-Feb-22	28-Feb-22	0%	0	-	Set OH	Power Poles				-				
NST-1010	Excavate & Backfill	20	20	01-Mar-22	28-Mar-22	0%	0	1	A CONTRACTOR OF THE PARTY OF TH	Excavatie & Ba	ckfill	1		i				
NST-1020	UG Mechanical	20	20	15-Mar-22	11-Apr-22	0%	0			UG Mech	anicai	1						
NST-1080	Pull OH Power Cables	5	5	29-Mar-22	04-Apr-22	0%	25	1		Pull OH Pov	ver Cables		li i	1				
NST-1030	LIG Flectrical	20	20	12-Apr-22	09-May-22	0%	0			U				1				
NST-1040	Form & Pour SOG Bldg #1	10	10	10-May-22	23-May-22	0%	0	·	†····			Pour SO	3 Bldg #	1				
NST-1050	Form & Pour SOG Bldg #2	10	10	17-May-22	31-May-22	0%	0				Form	& Pour S	OG Blda	#2				
NST-1060	Set Prefab Bldg #1	5	5	01-Jun-22	07-Jun-22	0%	0					Prefab Bl	910-2007					
NST-1070	Set Prefab Bldg #2	5	5	01-Jun-22	07-Jun-22	0%	0				47.0	Prefab Bl	100	1				
NST-1090	Install Landscaping	5	5	08-Jun-22	14-Jun-22	0%	0			1		stall Land	45					
Post Construct	The state of the s	12	12	15-Jun-22	30-Jun-22	0.0	0		+		V 10 2 - Co - C - C - C - C - C - C - C - C -			Constru	etion		-	
Closeout Subn		2	2	15-Jun-22	16-Jun-22		10			i	₩ 1	6-Jun-22	Closeou	t Submitt	als			
CLS-1000	Submit O&M Manuals	1	1	15-Jun-22	15-Jun-22	0%	10	1			1 1 10 10 10 10 10 10 10 10 10 10 10 10	ubmit O8						
CLS-1010	Submit As-Builts	1	1	15-Jun-22	15-Jun-22	0%	10				18	ubmit As-	Builts					
CLS-1030	R/A O&M Manuals	1	1	16-Jun-22	16-Jun-22	0%	10			1	1.5	M&O AU	Manuals	1				
CLS-1040													s	1				
Closeout Act	ACE301 sche	dule	e aj	opro	ved	ba	seli	ine	? .				10.10	seout Act r Pre-Fina	1000000	on		
CLS-1050	Perform Contractor Pre-Final Punchlist	2	2	16-Jun-22	17-Jun-22	0%	0				1	Perform (Contracto	r Pre-Fina	al Punchi	st		
CLS-1060	Perform O/A Pre-Final Inspection	1.	1	20-Jun-22	20-Jun-22	0%	0		1 1					Final Insp				
CLS-1070	Perform O/A Pre-Final Punchlist	5	5	21-Jun-22	27-Jun-22	0%	0		1			Perform	n O/A Pr	e-Final P	unchlist	1		
CLS-1080	Perform Final Inspection	1	1	28-Jun-22	28-Jun-22	0%	0					i Perfor	m Final I	napection				
CLS-1090	Perform Final Punchlist	1	1	29-Jun-22	29-Jun-22	0%	0					Perfor	m Final F	unchlist				
CLS-1100	Demoblize	1	1	30-Jun-22	30-Jun-22	0%	0		# W			Demo	blize		1			





Example Problem ACE301 Prefab Building

Impact:

 The contractor discovered a 55-gallon barrel with unknown contents on March 14 while excavating the building foundation.




Step 1 – Schedule Selection

Select the appropriate schedule to be impacted.

- Use the last updated schedule prior to the impact (reference the data date).
- If the time frame between previous schedule update and the impact is too great, progress the last schedule up to the point of impact.



Step 1 – Schedule Selection





Step 2 – Delay Fragnet Insertion

Prepare a schedule fragnet that models the delay or impact.

- The contractor is responsible for preparing the fragnet.
- The final fragnet must be approved or accepted by the government.



Definition of a Fragnet



A *fragnet* is defined as a sequence of new activities and/ or activity revisions that are proposed to be added to the existing schedule.



Their purpose is to demonstrate the influence of delay and the method for incorporating delays and impacts into the schedule as they are encountered.



Preparing a Fragnet

1

Determine the scope and extent of the impact encountered, either alleged or directed. 2

Identify possible corrective actions and select the best option.

3

Identify all impacted activities in the schedule.

4

Prepare a fragnet that best represents the total scope of the impact and corrective action.

5

Keep the fragnet simple.



Preparing a Fragnet



55-gallon barrels was discovered March 14, 2022.



Activity NST1010, Excavate & Backfill is impacted. Successor Activities are NST-1020 UG Mechanical and NST-1030 UG Electrical.



The owner requires 10 days to review and approve the plan before a NTP can be issued.



Testing the contents of the drum will take 10 days.



It will take the contractor 5 days to remove and dispose of the drums.



Preparing a Fragnet

Fragnet For Time Impact Analysis No. 1 (TIA1)






Step 3 – Insert Fragnet & Tie Logic

Insert the fragnet into the appropriate schedule.

- Select method for inserting the fragnet into the schedule.
- Assign settings, resources, codes, WBS, calendars, durations and predecessor/ successor logic.




Inserting the Fragnet into the Schedule






Example Problem ACE301 Prefab Building




Check Default Calendars

- As you add new activities, the default calendar will be assigned to them.
- Ensure the 5 Day Work Week Project Level Calendar is the Default* or applicable calendar.
- Check Default Settings and for activities





Create WBS for Fragnet






Create Activities for Fragnet & Tie Logic

Activity ID	Activity Name	Org Dur Rem D		Start	Finish	Phy %	Total Float	
Baseline Exa	mple ACE301- Update DD Feb 28 2022 TIA#1	175	141	25-Jan-22 A	18-Jul-22		-18	
- Milestones	MILE-1000 Notice to Proceed		0	25-Jan-22 A	18-Jul-22		-18	
MILE-1000	Notice to Proceed	0	0	25-Jan-22 A		100%		
MILE-1010	CCD- Contract Completion Date	0	0		18-Jul-22*	0%	-18	
□ Delays		25	25	14-Mar-22	15-Apr-22		-11	
■ TIA#1- Drum	Discovered	25	25	14-Mar-22	15-Apr-22		-11	
TIA-10	Govt/Cont. Negotiations - Drum Discovery	10	10	14-Mar-22*	25-Mar-22	0%	-11	
TIA-20	Test Drum Contents	10	10	28-Mar-22	08-Apr-22	0%	-11	
TIA-30	Remove/Dispose of Drum	5	5	11-Apr-22	15-Apr-22	0%	-11	
		2.0	2000		Esperant Control		3.5	

- 1. As you add new activities, the default calendar and settings will be added to each of the new activities.
- 2. As you add activities, edit the durations to match the duration provided.
- 3. Tie out the logic relationships, as seen above.





Constrained Start of Delay



ACE

Renumber Activity ID's





- 1. As you add new activities, the default ID # will be assigned.
- 2. Update the Activity ID to be unique to the delay.
 - le. TIA-10

Fragnet Schedule After Insertion

lay E	Achiji Name	Orgitur	Rembur	Sizi	Fean	Pity%	Tide (Co.)		her	Dr 2, 2022 May	Jan	и	Or1,3022	_
Reseline Evan	nple ACE301- Update DD Feb 28 2022 TIAN1	175	161	25-Jan-22 A	16-14-22		- 51	Mar.	Apr	May	An .		Baseline Example ACE301-	Update
Milestones	THE PROPERTY OF THE PARTY OF TH	175	0	25-Jan-22 A	18-Jul-22	_	-18		ļ			18-Jul-22,	6Nestones	
MILE-1000	Notice to Proceed	0	0	25-Jan-22 A		100%								
MILE-1010	CCD- Contract Completion Date	0	0		18-Jul-22*	0%	-18		D 0			CCD- Cor	fract Completion Date	
Delays		25	25	14-Mar-22	15-Aor-22		-1		15-Apr-22, D	plays		2700-00-00-00-		
TIA#1- Drum	Discovered	25	25	14-Mar-22	15-Aor-22		-11	······	15-Apr-22, TI	A#1- Drum Discovered	†····	 		-
TIA-10	Govt/Cont. Negotiations - Drum Discovery	10	10	14-Mar-22*	25-Mar-22	0%	-11	Gov	Cont. Negotiations - Drum D	scovery				
TIA-20	Test Drum Contents	10	10	28-Mar-22	08-Apr-22	0%	-11	_	Test Drum Contents	1252				
TIA-30	Remove/Dispose of Drum	5	5	11-Apr-22	15-Apr-22	0%	-11		Remove/Disp	ose of Drum				
Pre-Construc	tion	89	66	25-Jan-22 A	31-May-22		2				31-May-22, Pre-Construction	n .		
Submittal De	welopment	5	0	25-Jan-22 A	31-Jan-22 A			velopment	1		1	1		-
SDEV-1000	Submit Div 3- Concrete Submittal	1	0	25-Jan-22 A	25-Jan-22 A	100%		H .						
SDEV-1010	Submit Prefab Bidg Shops	5	0	25-Jan-22 A	31-Jan-22 A	100%								
Submittal Re	wiew & Approval	9	0	26-Jan-22 A	07-Feb-22-A			ittal Review & Approval	B 8			ĺ		
R&A-1000	R/A Div 3: Concrete Submittal	1	0	26-Jan-22 A	26-Jan-22 A	100%		vocaselia i caveneri interi	li			1		
R&A-1010	R/A Prefab Bldg Shops	5	0	01-Feb-22 A	07-Feb-22 A	100%		ops	1		1	1	1	-
Long Load P	rocurement	79	66	06 Feb-22 A	31-May-22		- 0		1		31-May-22, Long Lead Pro	durement		
FAB-1000	Fabricate & Deliver Prefab Bidg	79	66	08-Feb-22-A	31-May-22	16%	(1		Fabricate & Deliver Prefab	Bldg		
Construction		110	87	25-Jan-22 A	29-Jun-22		-11					29-Jun-22, Construction		
Site Prep		5	0	25-Jan-22 A	31-Jan-22 A									1
MOB-1000	Site Survey	1	0	25-Jan-22 A	25-Jan-22 A	100%			1		1	1		
MOB-1010	Clear & Grub	3	0	26-Jan-22 A	26-Jan-22 A	100%								
MOB-1020	Install Erosion Control	3	0	27-Jan-22 A	31-Jan-22 A	100%			E 8					
Foundations	& Structure	105	87	01-Feb-22 A	29-Jun-22		-11				-	29-Jun-22, Foundations & St	ucture	
NST-1000	Set OH Power Poles	19	0	01-Feb-22 A	28-Feb-22 A	100%		Set OH Power Poles						
NST-1010	Excavate & Backfill	20	20	28-Feb-22	25-Mar-22	056	-	Exc	avate & Backfill		†	†		-
NST-1080	Pull OH Power Cables	5	5	28-Mar-22	01-Apr-22	0%	26	· -	Pull OH Power Cables					
NST-1020	UG Mechanical	20	20	18-Apr-22	13-May-22	0%	-11			UG Mechanica	al			
NST-1030	UG Electrical	20	20	27-Apr-22	24-May-22	0%	-11			UG UG	Electrical			
NST-1040	Form & Pour SOG Bidg #1	10	10	25-May-22	08-Jun-22	0%	-11				Form & Pour SOG		Escapa a construction and a second	- 1
NST-1050	Form & Pour SOG Bidg #2	10	10	02-Jun-22	15-Jun-22	0%	-11		Ì		Form & Pour	SOG Bldg #2		
NST-1060	Set Prefab Bidg #1	5	5	09-Jun-22	15-Jun-22	0%	-4				Set Prefab B	lidg#1	3	
NST-1070	Set Prefab Bidg #2	5	5	16-Jun-22	22-Jun-22	0%	-11				Set P	refab Bldg #2		
NST-1090	Install Lanscaping	5	5	23-Jun-22	29-Jun-22	0%	-11					Install Lanscaping		1
Post Constru	ction .	12	12	30-Jun-22	18-Jul-22		-1				,		Post Construction	
Closeout Su	bmittals	2	2	30-Jun-22	01-34-22		- 4			45.11		01-Jul-22, Closeout Submi	bis	
CLS-1000	Submit O&M Manuals	1	1	30-Jun-22	30-Jun-22	0%	-					Submit O&M Manuals		
CLS-1010	Submit As-Builts	1	1	30-Jun-22	30-Jun-22	0%	- 4	1				Submit As-Builts		
CLS-1030	R/A O&M Manuals	1	1	01-Jul-22	01-Jul-22	0%	-					R/A O&M Manuals		
CLS-1040	R/AAs-Buits	1	1	01-Jul-22	01-Jul-22	0%	- 4					R/AAs-Builts		
Closeout Ac	tivities	12	12	30-Jun-22	18-Jul-22		-11		18				Closeout Activities	
CLS-1020	Perform Contractor Pre-Final Inspection	1	1	30-Jun-22	30-Jun-22	0%	-11					Perform Contractor Pre-Fin		
CLS-1050	Perform Contractor Pre-Final Punchtist	2	2	01-Jul-22	05-Jul-22	0%	-11					Perform Contractor Pre		
CLS-1060	Perform O/A Pre-Final Inspection	1	1	06-Jul-22	06-Jul-22	0%	-11	1				Perform O/A Pre-Fina		
CLS-1070	Perform O/A Pre-Final Punchilist	5	5	07-Jul-22	13-Jul-22	0%	-11	l				Perform O/A P		
CLS-1000	Perform Final Inspection	1	1	14-Jul-22	14-Jul-22	056	-11				1	Perform Final	respection	
CLS-1090	Perform Final Punchlist	1	1	15-Jul-22	15-Jul-22	046	-11		8			Perform Fina		
CLS-1100	Demoblize	1	1	18-Jul-22	18-Jul-22	056	-11	I				■ Demobilize		1



Step 4 – Review Dates & Changes

Now that the fragnet (including durations) has been inserted into the schedule:

- 1. Note project completion date for the last activity, "CCD Contract Completion Date".
- 2. Recalculate the CPM.
- 3. Note any changes to the project completion date.
- 4. Note any changes to interim



Step 4 – Review Dates & Changes



Note: Project Completion Date is June 30, 2022 prior to recalculating the schedule.



Note Any Changes to the CCD

- If the project completion date slipped, then the critical path was impacted, and the contractor is owed time.
- If applicable, note whether other contractual date(s) slipped.

In the Example:

- After TIA added, CCD is July 18, 2022, with -18 calendar days of negative total float.
- Meaning that the schedule is now 18 calendar days behind schedule(impacted) after the TIA Delay was inserted.



Step 5 – Days Owed

Determine the number of days owed to the contractor.

Remember, the contractor is owed calendar days, not workdays.

livity ID	Calendar Activity Name	Org Dur	Ram Dur	Start	Frish	Phy %	Total Floa
Baseline Example ACE301-Update DD	Feb 28 2022 TI/	127	127	14-Mar-22	18-Jul-22		
Milestones	- Day Calcida	0	0	18-Jul-22	18-Jul-22		- 4
MILE-1010	7Day Calendar CCD- Contract Completion Date	0	0	Control Control	18-Jul-22*	0%	-1
Delays	TDay Calendar	25	25	14-Mar-22	15-Apr-22		- 3
TIA#1- Drum Discovered	7Day Calendar	25	25	14-Mar-22	15-Apr-22		- 4
TIA-10	5 Day Calendar Govt/Cont. Negotiations - Drum Discovery	10	10	14-Mar-22*	25-Mar-22	0%	- 2
TIA-20	5 Day Calendar Test Drum Contents	10	10	28-Mar-22	08-Apr-22	0%	- 2
TIA-30	5 Day Calendar Remove/Dispose of Drum	5	5	11-Apr-22	15-Apr-22	0%	-
Construction	5 Day Calendar	52	52	18-Apr-22	29-Jun-22		1 1
Foundations & Structure	5 Day Calendar	52	52	18-Apr-22	29 Jun 22		1 3
NST-1020	5 Day Calendar UG Mechanical	20	20	18-Apr-22	13-May-22	0%	-
NST-1030	5 Day Calendar UG Electrical	20	20	27-Apr-22	24-May-22	0%	
NST-1040	5 Day Calendar Form & Pour SOG Bldg #1	10	10	25-May-22	08-Jun-22	0%	2
NST-1050	5 Day Calendar Form & Pour SOG Bldg #2	10	10	02-Jun-22	15-Jun-22	0%	3
NST-1070	5 Day Calendar Set Prefab Bldg #2	5	5	16-Jun-22	22-Jun-22	0%	1
NST-1090	5 Day Calendar Install Lanscaping	5	5	23-Jun-22	29-Jun-22	0%	-
Post Construction	5 Day Calendar	12	12	30-Jun-22	18-Jul-22		- 4
Closeout Activities	5 Day Galendar	12	12	30-Jun-22	18-Jul-22		
CLS-1020	5 Day Calendar Perform Contractor Pre-Final Inspection	1	1	30-Jun-22	30-Jun-22	0%	- 0
CLS-1050	5 Day Calendar Perform Contractor Pre-Final Punchlist	2	2	01-Jul-22	05-Jul-22	0%	2
CLS-1060	5 Day Calendar Perform O/A Pre-Final Inspection	1	1	06-Jul-22	06-Jul-22	0%	
CLS-1070	5 Day Calendar Perform O/A Pre-Final Punchlist	5	5	07-Jul-22	13-Jul-22	0%	- 2
CLS-1080	5 Day Calendar Perform Final Inspection	1	1	14-Jul-22	14-Jul-22	0%	2
CLS-1090	5 Day Calendar Perform Final Punchlist	1	1	15-Jul-22	15-Jul-22	0%	
CLS-1100	5 Day Calendar Demoblize	1	1	18-Jul-22	18-Jul-22	0%	1 2

Golden Rule: By Assigning all milestones a 7 Day calendar, your CCD will always calculate the correct days owed in calendar days for you.



Step 6 – Determine Delay Dates

Determine the actual delay dates.

The start of delay begins on the first day that the project completion date slips and ends when the remaining delay days are exhausted.



Step 6 – Determine Delay Dates

A rule of thumb for determining the actual delay dates is to identify successor activity(s) to the fragnet in the schedule used in the TIA prior to inserting the fragnet.

The first day of delay will be predicated on the date when the successor activity in the fragnet to become project critical:

<u>Successor Activities Without Negative Float</u> - The successor activity will become project critical on the computed late start date. If there are multiple successors, choose the earliest late start date. The first day of delay will be the next day after this late start date.

<u>Successor Activities With Negative Float</u> - If successor activities have negative float, then the start of delay is the first day of the impact.



Step 7 – Excusable and/or Compensable

Determine if the delay is:

- Excusable Contractor owed time.
- Compensable Receives extended project costs.

If the contractor has a concurrent <u>critical path delay</u>, then the delay is excusable, but not compensable.

If there are *no* concurrent contractor <u>critical path delays</u>, then the delay is excusable and compensable.

Force Majeure or Acts of God delays are excusable, but not compensable.



Step 8 – Documentation

Document the time impact analysis in a price negotiation memorandum and in the modification:

- Description of the impact or changed condition and other facts and assumptions used in the TIA.
- Maintain hard and electronic copies (.xer file) of the unimpacted and impacted schedules used in the TIA.
- Description of each fragnet activity including, durations, calendars, and predecessor and successor logic.
- Describe the results of the time impact analysis including time owed to the contractor, actual delay dates, extended project costs, etc.





<u>Questions</u>



Let's Connect! ACE Training



dhagan@ace-consulting.net



ace-consulting.net



ACE Consulting Company, LLC

